

IN THE CLAIMS:

Substitute the following claims for the pending claims having the same numbers.

1. (currently amended) A system for making fiber optic connections in a subterranean well, the system comprising:

a first fiber optic connector positioned in the well; and

a second fiber optic connector operatively connected to the first fiber optic connector after the first fiber optic connector is positioned in the well, a connection between the first and second fiber optic connectors being made after the first and second fiber optic connectors are positioned in the well , and the second fiber optic connector being operatively coupled to an optical line which senses temperature within a gravel packing assembly.
2. (original) The system according to claim 1, wherein the first fiber optic connector is operatively coupled to a fiber optic line which is configured to sense a downhole parameter.
3. (original) The system according to claim 1, wherein the first fiber optic connector is operatively coupled to a fiber optic line which has a sensor connected thereto.
4. (original) The system according to claim 1, wherein the first fiber optic connector is attached to a first downhole assembly, wherein the second fiber optic connector is attached

to a second downhole assembly, and wherein the first and second assemblies are attached to each other downhole, thereby operatively connecting the first and second fiber optic connectors.

5. (original) The system according to claim 4, wherein the first and second assemblies are rotationally oriented with respect to each other prior to operatively connecting the first and second fiber optic connectors.

6. (canceled)

7. (canceled)

8. (original) The system according to claim 1, wherein at least one of the first and second fiber optic connectors is operatively coupled to a fiber optic line extending longitudinally through a packer.

9. (original) The system according to claim 1, wherein the first fiber optic connector is operatively coupled to a first fiber optic line positioned external to a tubular string in the well, and wherein the second fiber optic connector is operatively coupled to a second fiber optic line positioned internal to the tubular string.

10. (original) The system according to claim 1, wherein the first fiber optic connector is attached to a tubular string, and wherein the second fiber optic connector is attached to an assembly received within the tubular string.

11. (currently amended) A system for making fiber optic connections in a subterranean well, the system comprising:

a first assembly positioned in the well, the first assembly including a first fiber optic connector;

a second assembly positioned in the well, the second assembly including a second fiber optic connector , and the second fiber optic connector being operatively coupled to an optical line which senses temperature within a gravel packing assembly; and

an orienting device orienting the first assembly relative to the second assembly, thereby aligning the first and second fiber optic connectors, a connection between the first and second fiber optic connectors being made after the first and second fiber optic connectors are positioned in the well.

12. (canceled)

13. (canceled)

14. (original) The system according to claim 11, wherein the first assembly is a tubular string, and wherein the second assembly is received within the tubular string.

15. (original) The system according to claim 14, wherein the second assembly is conveyed on a running tool through the tubular string.

16. (original) The system according to claim 15, wherein pressure applied between the running tool and the tubular string causes the first and second fiber optic connectors to operatively connect with each other.

17. (original) The system according to claim 11, wherein at least one of the first and second fiber optic connectors is operatively coupled to a fiber optic line extending through a packer in the well.

18. (original) The system according to claim 11, wherein the first fiber optic connector is operatively coupled to a first fiber optic line positioned external to a tubular string, and wherein the second fiber optic connector is operatively connected to a second fiber optic line positioned internal to the tubular string.

19. (withdrawn) The system according to claim 11, wherein the first and second fiber optic connectors are operatively coupled to respective ones of first and second fiber optic lines positioned external to a tubular string.

20. (original) The system according to claim 11, wherein at least one of the first and second fiber optic connectors is operatively coupled to a fiber optic line configured to sense a parameter in the well.

21. (original) The system according to claim 11, wherein at least one of the first and second fiber optic connectors is operatively coupled to a fiber optic line attached to a sensor for sensing a parameter in the well.

22. (original) The system according to claim 11, wherein the first assembly is a receptacle interconnected in a tubular string in the well, and wherein the second assembly is releasably secured in the receptacle.

23. (original) The system according to claim 22, wherein the first and second connectors are operatively connected in response to pressure applied to the receptacle.

24. (original) The system according to claim 22, wherein the second assembly extends into a third assembly positioned in the well.

25. (currently amended) The system according to claim 24, wherein the third assembly is a the gravel packing assembly.

26. (original) The system according to claim 24, wherein the third assembly is positioned in the well prior to conveying the first assembly into the well.

27. (canceled) The system according to claim 24, wherein the second assembly includes a fiber optic line operatively coupled to the second fiber optic connector, the fiber optic line extending into the third assembly.

28. (original) The system according to claim 27, wherein the fiber optic line transmits an indication of a parameter sensed in the third assembly.

29. (original) The system according to claim 27, wherein the fiber optic line is positioned external to the second assembly in the third assembly.

30. (original) The system according to claim 27, wherein the fiber optic line is positioned internal to the second assembly in the third assembly.

31. (original) The system according to claim 11, wherein pressure applied to the first assembly causes operative connection of the first and second fiber optic connectors.

32. (currently amended) A method of making fiber optic connections in a subterranean well, the method comprising the steps of:

positioning a first assembly in the well, the first assembly including a first fiber optic connector;

positioning a second assembly in the well, the second assembly including a second fiber optic connector;

operatively coupling the second fiber optic connector to an optical line which senses temperature within a gravel packing assembly;

orienting the first and second assemblies in the well, thereby aligning the first and second fiber optic connectors; and

then operatively connecting the first and second fiber optic connectors in the well.

33. (original) The method according to claim 32, wherein the orienting step further comprises rotationally orienting the first and second assemblies.

34. (original) The method according to claim 32, further comprising the step of attaching the second assembly to the first assembly.

35. (original) The method according to claim 34, wherein the attaching step further comprises securing the second assembly within the first assembly.

36. (original) The method according to claim 32, further comprising the step of sealing between the first and second assemblies.

37-45. (canceled)

46. (currently amended) An apparatus for making a connection between lines in a subterranean well, the apparatus comprising:

an outer housing having a sidewall, and a passage extending through the housing;

a first connector positioned in the housing sidewall; and

a second connector received within the passage, the first and second connectors being operatively connectable after the apparatus is positioned in the well, a connection between the first and second connectors being made after the first and second connectors are positioned in the well , and the second connector being operatively coupled to an optical line which senses temperature within a gravel packing assembly.

47. (original) The apparatus according to claim 46, wherein the first connector is attached to a piston reciprocally received in the housing sidewall.

48. (original) The apparatus according to claim 47, wherein pressure applied to the piston displaces the first connector into operative engagement with the second connector.

49. (original) The apparatus according to claim 47, wherein the second connector is attached to an assembly received within the passage, pressure applied through the assembly causing the first and second connectors to operatively engage.

50. (original) The apparatus according to claim 49, wherein the assembly includes a fiber optic line operatively coupled to the second connector, the fiber optic line extending longitudinally within the passage.

51. (canceled)

52. (original) The apparatus according to claim 49, further comprising an orienting profile which rotationally orients the assembly relative to the housing, thereby aligning the first and second connectors.

53. (original) The apparatus according to claim 49, further comprising an anchoring device which releasably secures the assembly relative to the housing.

54. (original) The apparatus according to claim 46, wherein each of the first and second connectors is a fiber optic connector.

55. (original) The apparatus according to claim 46, wherein at least one fiber optic line is coupled to each of the first and second connectors.

56. (original) The apparatus according to claim 46, wherein multiple types of lines are coupled to each of the first and second connectors.

57. (original) The apparatus according to claim 46, wherein a selected one or more of fiber optic, electrical and hydraulic lines are coupled to each of the first and second connectors.

58-69. (canceled)

70. (currently amended) A system for making fiber optic connections in a subterranean well, the system comprising:

a tubular string including a passage formed through the tubular string, and a first fiber optic connector; and

an assembly received in the passage, the assembly including a second fiber optic connector, a connection between the first and second fiber optic connectors being made after the first and second fiber optic connectors are positioned in the well , and the second fiber optic connector being operatively coupled to an

optical line which senses temperature within a gravel packing assembly.

71. (original) The system according to claim 70, wherein the first and second connectors are operatively connected to each other after the tubular string is positioned in the well.

72. (original) The system according to claim 70, wherein the tubular string includes a first orienting device, wherein the assembly includes a second orienting device, and wherein engagement between the first and second orienting devices aligns the first and second fiber optic connectors.

73. (original) The system according to claim 70, wherein pressure applied to at least one of the tubular string and the assembly causes relative displacement between the first and second fiber optic connectors, thereby causing the first and second fiber optic connectors to operatively connect.

74. (original) The system according to claim 70, wherein pressure applied to at least one of the tubular string and the assembly causes relative displacement between the first and second fiber optic connectors, thereby causing the first and second fiber optic connectors to operatively disconnect.

75. (original) The system according to claim 70, wherein the second fiber optic connector is operatively coupled to a sensor of the assembly.

76. (canceled)

77. (original) The system according to claim 75, wherein the sensor monitors temperature distributed along the assembly.

78. (original) The system according to claim 75, wherein the sensor identifies a location of influx of water from a formation intersected by the well.

79. (original) The system according to claim 70, wherein the first fiber optic connector is operatively coupled to a fiber optic line extending external to the tubular string.

80. (withdrawn) The system according to claim 70, wherein the assembly is positioned in the passage when the tubular string is installed in the well, and wherein the assembly is displaced in the passage, thereby operatively connecting the first and second fiber optic connectors, after the tubular string is installed in the well.

81. (original) The system according to claim 70, wherein the assembly is positioned and displaced in the passage, thereby operatively connecting the first and second fiber optic connectors, after the tubular string is installed in the well.

82. (original) The system according to claim 70, wherein the assembly is secured to the tubular string when the assembly is received in the passage.

83. (original) A method of monitoring a subterranean well, the method comprising the steps of:

positioning a first fiber optic line in the well, the first fiber optic line extending in a formation intersected by the well;

positioning a second fiber optic line in the well, the second fiber optic line extending to a remote location;

operatively connecting the first and second fiber optic lines while the first and second fiber optic lines are in the well; and

monitoring a well parameter using a sensor operatively coupled to the first fiber optic line.

84. (original) The method according to claim 83, wherein in the monitoring step the sensor is a portion of the first fiber optic line.

85. (original) The method according to claim 83, wherein the monitoring step further comprises using the sensor to sense a selected one or more of seismic, pressure, temperature, water cut, flow rate, radioactivity and phase parameters.

86. (original) The method according to claim 83, wherein in the monitoring step there are multiple ones of the sensor distributed along the first fiber optic line.

87. (original) The method according to claim 83, wherein the monitoring step further comprises monitoring well temperature distributed along the first fiber optic line.

88. (original) The method according to claim 83, wherein the monitoring step further comprises identifying a location of influx of water from the formation into the well.